

BEAM & TRUSS POSITION SCHEDULE / INCHES

Member	Type	Start (X, Y)	End (X, Y)	Ref. length	Bottom Z
B-WO	beam	(-34, -66)	(-34, 269)	335.00	98.5
B2	beam	(-34, 185)	(211.5, 185)	245.50	98.5
B3	beam	(-34, 249)	(211.5, 249)	245.50	98.5
C-EM	beam	(246.5, 185)	(211.5, 185)	35.00	98.5
C-EN	beam	(247.5, 251)	(211.5, 251)	36.00	98.5
C-ES	beam	(247.5, -2)	(211.5, -2)	36.00	98.5
E-OB	beam	(247.5, -4)	(247.5, 253)	257.00	98.5
O2	subsegment	(-34, 69.75)	(0, 69.75)	34.00	98.5
O3	subsegment	(-34, 185)	(0, 185)	34.00	98.5
OB1	context beam	(-164.25, 174)	(-27, 174)	137.25	unknown
T-E	truss	(211.5, -64)	(211.5, 269)	333.00	98.5
T-N	truss	(-34, 269)	(211.5, 269)	245.50	98.5
T-S	truss	(-34, 0)	(211.5, 0)	245.50	98.5
T-SO	beam	(-34, -64)	(211.5, -64)	245.50	98.5
T-W	truss	(-34, -66)	(-34, 269)	335.00	98.5
T1	truss	(-34, 69.75)	(211.5, 69.75)	245.50	98.5

Plan lines are reference axes, not solid member envelopes. Lengths are not fabrication cuts.
Draft positions and source assumptions are itemized in coordination-report.md. E-OB uses a provisional 3-inch display envelope. OB1 elevation is unknown.