

SUPPORT POSITION SCHEDULE / INCHES

Support	Center X	Center Y	Plan symbol	Status	Base / top Z
E-M	246.5	185	4 × 4	B only	0 / 98.5 trial
E-N	247.5	251	4 × 4	A and B	0 / 98.5 trial
E-S	247.5	-2	4 × 4	A and B	0 / 98.5 trial
N1	19.5	269	4 × 4	proposed	0 / 98.5
N2	211.5	269	4 × 4	proposed	0 / 98.5
S1	148.5	-66	4 × 4	proposed	0 / 98.5
S2	211.5	-66	4 × 4	proposed	0 / 98.5
S3	211.5	-2	4 × 4	proposed	0 / 98.5
W1	-34	-66	4 × 4	proposed	0 / 98.5
W2	-34	69.75	4 × 4	proposed	0 / 98.5
W3	-34	185	4 × 4	proposed	0 / 98.5
W4	-34	269	4 × 4	proposed	0 / 98.5
WB3	-2	185	4 × 4	proposed	0 / 98.5

SW exterior garage corner is X=0, Y=0. Symbol dimensions do not select structural sections.
All current support coordinates come from the floor-plan basis; E-M is an option-B support.